

METAL PLATE SYSTEMS



PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes modular metal plate wall panels.

1.2 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project site.
1. Meet with Owner, Architect, Owner's insurer if applicable, metal panel Installer, metal panel manufacturer's representative, structural-support Installer, and installers whose work interfaces with or affects metal panels, including installers of doors, windows, and louvers.
 2. Review and finalize construction schedule and verify availability of materials, Installer's personnel, equipment, and facilities needed to make progress and avoid delays.
 3. Review methods and procedures related to metal panel installation, including manufacturer's written instructions.
 4. Examine support conditions for compliance with requirements, including alignment between and attachment to structural members.
 5. Review flashings, special siding details, wall penetrations, openings, and condition of other construction that affect metal panels.
 6. Review governing regulations and requirements for insurance, certificates, and tests and inspections if applicable.
 7. Review temporary protection requirements for metal panel assembly during and after installation.
 8. Review procedures for repair of panels damaged after installation.
 9. Document proceedings, including corrective measures and actions required, and furnish copy of record to each participant.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for each type of panel and accessory.
- B. Shop Drawings:
1. Include fabrication and installation layouts of metal panels; details of edge conditions, joints, panel profiles, corners, anchorages, attachment assembly, trim, flashings, closures, and accessories; and special details.
 2. Accessories: Include details of the flashing, trim, and anchorage, at a scale of not less than 1-1/2 inches per 12 inches (1:10).
- C. Delegated Design Submittal: Submit for metal wall panel systems indicated to comply with performance requirements and design criteria, analysis data signed and sealed by the qualified professional engineer responsible for their preparation.
- D. Samples for Verification: For each type of exposed finish required, prepared on Samples of size indicated below.
1. Metal Panel Finish Chip: At least 2 inch by 3 inch

1.4 QUALITY ASSURANCE

- A. Installer Qualifications: An entity that employs installers and supervisors who are trained and approved by manufacturer.
- B. Mockups: Build mockups to verify selections made under Sample submittals and to demonstrate aesthetic effects and set quality standards for fabrication and installation.
1. Build mockup of typical metal panel assembly as directed by Architect, including corner, supports, attachments, and accessories.
 2. Approval of mockups does not constitute approval of deviations from the Contract Documents contained in mockups unless Architect specifically approves such deviations in writing.
 3. Subject to compliance with requirements, approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

1.5 DELIVERY, STORAGE, AND HANDLING

- A. Deliver components, metal panels, and other manufactured items so as not to be damaged or deformed. Package metal panels for protection during transportation and handling.

METAL PLATE SYSTEMS



- B. Unload, store, and erect metal panels in a manner to prevent bending, warping, twisting, and surface damage.
 - C. Stack metal panels platforms or pallets, covered with suitable weathertight and ventilated covering. Store metal panels to ensure dryness, with positive slope for drainage of water. Do not store metal panels in contact with other materials that might cause staining, denting, or other surface damage.
 - D. Retain strippable protective covering on metal panels during installation.
- 1.6 FIELD CONDITIONS
- A. Weather Limitations: Proceed with installation only when existing and forecasted weather conditions permit assembly of metal panels to be performed according to manufacturers' written instructions and warranty requirements.
- 1.7 COORDINATION
- A. Coordinate metal panel installation with rain drainage work, flashing, trim, construction of soffits, and other adjoining work to provide a leakproof, secure, and noncorrosive installation.
- 1.8 WARRANTY
- A. Manufacturer's Warranty: Manufacturer's standard form in which manufacturer agrees to repair or replace components of metal panel systems that fail in materials or workmanship within specified warranty period.
 - 1. Finish:
 - a. Exposed Panel Finish: Deterioration includes, but is not limited to, the following:
 - Color fading more than 5 Hunter units when tested according to ASTM D 2244.
 - Chalking more than a No. 8 rating when tested according to ASTM D 4214.
 - Cracking, checking, peeling, or failure of paint to adhere to bare metal.
 - b. Finish Warranty Period: [20] [10] years from date of Substantial Completion.
 - B. Installer Warranty: Installer's written workmanship warranty signed by an authorized representative using installer's standard form agreeing to provide labor required to repair or replace work which exhibits defects. "Defects" is defined to include but not limited to deterioration or failure to perform as required.
 - 1. Warranty Period: Installer/fabricator shall warrant the installation to be free from workmanship Defects for a period of 1 year from date of substantial completion.

PART 2 - PRODUCTS

- 2.1 PERFORMANCE REQUIREMENTS
- A. Structural Performance: Provide metal panel systems capable of withstanding the effects of the following loads, based on testing according to ASTM E 330:
 - 1. Wind Loads: As indicated on Drawings.
 - 2. Other Design Loads: As indicated on Drawings.
 - 3. Deflection Limits for framing members normal to wall frame (panel perimeter): For wind loads, no greater than 1/175 of the span.
 - 4. Deflection of Panels: For short side panel edge dimension (L), limit center-of-panel deflection to not greater than L/60.
 - B. Air Infiltration: Air leakage of not more than 0.06 cfm/sq. ft. (0.3 L/s per sq. m) when tested according to ASTM E 283 at the following test-pressure difference:
 - 1. Test-Pressure Difference: 6.24 lbf/sq. ft. (300 Pa).
 - C. Water Penetration under Static Pressure: No water penetration when tested according to ASTM E 331 at the following test-pressure difference:
 - 1. Test-Pressure Difference: 6.24 lbf/sq. ft. (300 Pa).
 - D. Thermal Movements: Allow for thermal movements from ambient and surface temperature changes by preventing buckling, opening of joints, overstressing of components, failure of joint sealants, failure of connections, and other detrimental effects. Base calculations on surface temperatures of materials due to both solar heat gain and nighttime-sky heat loss.
 - 1. Temperature Change (Range): 120 deg F (67 deg C), ambient; 180 deg F (100 deg C), material surfaces.

METAL PLATE SYSTEMS



- E. Fire Propagation Characteristics: Metal wall panel system passes NFPA 285 testing.
- 2.2 MODULAR METAL WALL PANELS
- A. Manufacturers: : Basis-of-Design (BOD) Manufacturer, Model/Product: Vista Plate System by Form Metals Inc. Irving, Texas
 - B. System Type: Pressure equalized rainscreen system.
 - C. Aluminum Plate Panels
 - 1. Standard Panel Thickness: .080"
 - a. Additional Thickness Available (please contact Form Metal) - .063" , .125"
 - 2. Finish: [AAMA 2605 Powder Coat], [AAMA 2604 Powder Coat], [AAMA 2605 Two-Coat Painted Finish], [AAMA 2605 Three-Coat Painted Finish]
 - 3. Panel Depth: 1 ½ inch nominal
 - 4. Panel Size: As indicated on drawings.
 - 5. Panel Joints: As indicated on drawings
 - D. Attachment Assembly: Manufacturer's standard for installation system specified.
- 2.3 MISCELLANEOUS MATERIALS
- A. Miscellaneous Metal Subframing and Furring: ASTM C 645, cold-formed, metallic-coated steel sheet ASTM A 653/A 653M, G90 (Z275 hot-dip galvanized) coating designation or ASTM A 792/A 792M, Class AZ50 (Class AZM150) aluminum-zinc-alloy coating designation unless otherwise indicated. Provide manufacturer's standard sections as required for support and alignment of metal panel system.
 - B. Panel Accessories: Provide components required for a complete panel system including trim, copings, fasciae, mullions, sills, corner units and related items. Match material and finish of metal panels unless indicated otherwise.
 - C. Trim: Provide trim matching metal panels as required to provide finished appearance.
 - D. Panel Fasteners: Self-tapping screws designed to withstand design loads. Provide exposed fasteners if needed with heads matching color of metal panels by means of plastic caps or factory-applied coating. Provide EPDM or PVC sealing washers for exposed fasteners.
- 2.4 FABRICATION
- A. General: Fabricate metal panels and accessories at the factory, by manufacturer's standard procedures and processes, as necessary to fulfill indicated performance requirements demonstrated by laboratory testing. Comply with indicated profiles and with dimensional and structural requirements. Panels to be fabricated with machine automated shearing and bending.
 - B. Trim: Fabricate trim to comply with manufacturer's recommendations and recommendations in SMACNA's "Architectural Sheet Metal Manual" that apply to design, dimensions, metal, and other characteristics of item indicated.
 - 1. Form exposed sheet metal accessories that are without excessive oil canning, buckling, and tool marks and that are true to line and levels indicated, with exposed edges folded back to form hems.
 - 2. Seams for Aluminum: Fabricate nonmoving seams with flat-lock seams. Form seams and seal with epoxy seam sealer. Rivet joints for additional strength.
 - 3. Sealed Joints: Form non-expansion, but movable, joints in metal to accommodate sealant and to comply with SMACNA standards.
 - 4. Conceal fasteners and expansion provisions where possible. Exposed fasteners are not allowed on faces of accessories exposed to view.
 - 5. Fabricate cleats and attachment devices from same material as accessory being anchored or from compatible, noncorrosive metal recommended in writing by metal panel manufacturer.
 - a. Size: As recommended by SMACNA's "Architectural Sheet Metal Manual" or metal wall panel manufacturer for application but not less than thickness of metal being secured.
- 2.5 FINISHES
- A. Protect mechanical and painted finishes on exposed surfaces from damage by applying a strippable, temporary protective covering before shipping.

METAL PLATE SYSTEMS



- B. Appearance of Finished Work: Variations in appearance of abutting or adjacent pieces are acceptable if they are within one-half of the range of approved Samples. Noticeable variations in same piece are not acceptable. Variations in appearance of other components are acceptable if they are within the range of approved Samples and are assembled or installed to minimize contrast.
- C. Aluminum Panels and Accessories:
1. Superior-Performance Organic FEVE Fluoropolymer Powder Finish: Single-coat Fluoropolymer Powder finish complying with AAMA 2605. Prepare, pretreat and apply coating to exposed metal surfaces to comply with coating and resin manufacturer's written instructions.
 - a. Product Code: []
 - b. Color: []
 - c. Manufacturer: []
 - d. Contact: []
 - OR
 2. Superior Performance Organic Coating System: AAMA 2605 multiple coat, thermally cured polyvinylidene fluoride (PVDF) resin system. Prepare, pretreat and apply coating to exposed metal surfaces to comply with coating and resin manufacturers' installation instructions.
 - a. Two-Coat Fluoropolymer: AAMA 2605, fluoropolymer finish containing not less than 70 percent PVDF resin by weight in color coat.
 - b. Two-Coat Mica Fluoropolymer: AAMA 2605, fluoropolymer finish with suspended mica flakes containing not less than 70 percent PVDF resin by weight in color coat.
 - c. Three Coat Fluoropolymer: AAMA 2605, fluoropolymer finish containing not less than 70 percent PVDF resin by weight in both color coat and clear topcoat.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for installation tolerances, metal panel supports, and other conditions affecting performance of the Work.
1. Examine wall sheathing to verify that sheathing joints are supported by framing or blocking, and that installation is within flatness tolerances required by metal wall panel manufacturer.
 - a. Verify that air- or water-resistive barriers have been installed over sheathing or backing substrate to prevent air infiltration or water penetration.
- B. Examine roughing-in for components and assemblies penetrating metal panels to verify actual locations of penetrations relative to seam locations of metal panels before installation.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Miscellaneous Supports: Install subframing, furring, and other miscellaneous panel support members and anchorages according to ASTM C 754 and metal panel manufacturer's written recommendations.

3.3 MODULAR METAL PLATE PANEL INSTALLATION

- A. General: Install metal panels according to manufacturer's written instructions in orientation, sizes, and locations indicated on Drawings. Install panels perpendicular to supports unless otherwise indicated. Anchor metal panels and other components of the Work securely in place, with provisions for thermal and structural movement.
1. Do not begin installation until air- or water-resistive barriers and flashings that will be concealed by metal panels are installed.
 2. Shim or otherwise plumb substrates receiving metal panels.
 3. Install screw fasteners in predrilled holes.
 4. Locate and space fastenings in uniform vertical and horizontal alignment.
 5. Install trim as metal panel work proceeds.
 6. Locate panel splices over, but not attached to, structural supports. Stagger panel splices and end laps to avoid a four-panel lap splice condition.
 7. Align bottoms of metal panels and fasten with blind rivets, bolts, or self-tapping screws. Fasten trim around openings and similar elements with self-tapping screws.

METAL PLATE SYSTEMS



- B. Fasteners:
1. Aluminum Panels: Use aluminum or stainless-steel fasteners for surfaces exposed to the exterior; use aluminum or galvanized-steel fasteners for surfaces exposed to the interior.
- C. Metal Protection: Where dissimilar metals contact each other or corrosive substrates, protect against galvanic action as recommended in writing by metal panel manufacturer.
- D. Attachment Assembly, General: Install attachment assembly required to support metal wall panels and to provide a complete wall system, including subgirts, tracks, and drainage channels.
1. Include attachment to supports, panel-to-panel joinery, panel-to-dissimilar-material joinery, and panel-system joint seals.
- E. Installation: Attach metal wall panels to supports at locations, spacings, and with fasteners recommended by manufacturer to achieve performance requirements specified.
- F. Accessory Installation: Install accessories with positive anchorage to building and weathertight mounting and provide for thermal expansion. Coordinate installation with trim and other components.
1. Install components required for a complete metal panel assembly including trim, corners, and related items. Provide types indicated by metal panel manufacturer; or, if not indicated, provide types recommended in writing by metal panel manufacturer.
- G. Trim: Comply with performance requirements, manufacturer's written installation instructions, and SMACNA's "Architectural Sheet Metal Manual." Provide concealed fasteners where possible and set units true to line and level as indicated.
1. Install exposed trim that is without buckling and tool marks and that is true to line and levels indicated, with exposed edges folded back to form hems.
 2. Expansion Provisions: Provide for thermal expansion of exposed trim. Space movement joints at a maximum of 10 feet (3 m). Where lapped expansion provisions cannot be used or would not be sufficiently waterproof, form expansion joints of intermeshing hooked flanges, not less than 1 inch (25 mm) deep, filled with mastic sealant (concealed within joints).
- 3.4 ERECTION TOLERANCES
- A. Installation Tolerances: Shim and align metal wall panel units within installed tolerance of 1/4 inch in 20 feet (6 mm in 6 m), non-accumulative, on level, plumb, and location lines as indicated, and within 1/8-inch (3-mm) offset of adjoining faces and of alignment of matching profiles.
- 3.5 FIELD QUALITY CONTROL
- A. Testing Agency: The Owner may employ and pay a qualified independent testing agency to perform field quality control. Retesting of materials and installations failing to meet specified requirements shall be done at Contractor's expense.
- B. Metal wall panels will be considered defective if they do not pass test and inspections.
- C. Prepare test and inspection reports.
- 3.6 CLEANING AND PROTECTION
- A. Remove temporary protective coverings and strippable films, if any, as metal panels are installed, unless otherwise indicated in manufacturer's written installation instructions. On completion of metal installation, clean finished surfaces as recommended by metal panel manufacturer. Maintain in a clean condition during construction.
- B. After metal panel installation, clear weep holes and drainage channels of obstructions, dirt, and sealant.
- C. Replace metal panels that have been damaged or have deteriorated beyond successful repair by finish touchup or similar minor repair procedures.

END OF SECTION